



General Building Contractors
License #744198 CA #154926 AZ DIR#1000009060
1616 Sierra Madre Circle, Placentia, CA 92870 Ph: (800) 949-0203 Fx: (714) 666-1007

May 25, 2018

City of Lake Elsinore
130 S. Main Street
Lake Elsinore CA 92530

VIA EMAIL: gpapagos@verizon.net
PROJ: Launch Point, Lake Elsinore CA (**Option 1 Playground**)
ATTN: Gus Papagos

Thank you for giving Micon Construction the opportunity to bid on the Launch Point Playground Improvement project. We look forward to the prospect of working with you and providing you with a great playground! We are pleased to submit a proposal for the above-mentioned project per your request. The breakdown is as follows:

Miracle Install Option 1

- Provide Miracle Next Generation modular play structure.
- Provide & maintain temp fencing.
- Excavate for EWF section, grade & prepare sub grade.
- Construct concrete containment curb w/ (2) # 4 cont rebar.
- Install Miracle Custom Tree House modular play structures.
- Construct (1) ADA fluctuation ramps.
- Excavate, construct (2) drainage sumps w/ geotextile fabric and aggregate.
- Provide & Install EWF w/ impact mats.

TOTAL: \$ 256,903.00

Additive Alternate

- Delete Engineered Wood Fiber, impact mats & installation. Construct sub base w/ concrete anchor. Provide resilient rubber surfacing up to 12' CFH. Include color separations w/ 50/50 blend standard color/ black. Bisecting river w/ 100% color.

\$ 73,516.00

Price based on all work concurrent. (1) move.
If you have any questions please feel free to call.

Sincerely,

MICON CONSTRUCTION

Exclusions: Irrigation renovations/repairs. Hardscape removals, connect to storm drain, painting, permits, fees, bonds, any unforeseen conditions, footing spoils, demolition and removals, not responsible for turf, landscape, utility repairs, and irrigation renovations unless noted above.
This quote is good for 30 days. Price based on one (1) move on and "tailgate" access to work. Minimum of \$ 600.00 for each additional move-on. No retention. Payment within 30 days. Applicable sales tax(es) will be added to total price on invoice. Area to be sub-grade ready. Quote based on all mentioned work as concurrent. Micon will off-load equipment if site is ready and delivery has been scheduled to coincide with installation. All work to be installed by certified CPSI installer and conform to CPSC and ASTM guidelines.



Manufacturer Certified Installer