



## **REPORT TO CITY COUNCIL**

**To:** Honorable Mayor and Members of the City Council  
**From:** Grant Yates, City Manager  
**Date:** August 13, 2019  
**Subject:** Camino del Norte Haul Route

### **Recommendation**

Approve the request for the Haul Route including the hours of operation.

### **Background**

In August of 2010, the City Council passed Ordinance 1271. The Ordinance requires all projects with transportation of earth materials in excess of 5,000 cubic yards to have their haul routes approved by the City Council. Riverside Construction Co is requesting approval of a haul route to be used during the project's fill import phase.

### **Discussion**

Work has commenced on the construction of the missing link of Camino del Norte between Main Street and Canyon Estates Drive. Import of material is required to raise the finish surface elevation of the road. The contractor will need approximately 15,680 CY of material, and the material will be coming from the nearby Nichols Mine.

Travel from import site (Loaded Trucks)

- Nichols Road to I-15
- I-15 to Main Street
- Main Street to Construction site

Return to import site (Empty Trucks)

- Construction site to Main Street
- Main Street to I-15
- I-15 to Nichols Road

The approved hours of work will be from 7:00 am-3:00 pm, to minimize the impact on rush hour traffic. Once commenced, the import will continue for 8 working days. The contractor will be required to provide video log through a 3<sup>rd</sup> party independent company of the condition of the

haul route prior to the start of work. The contractor will also post a \$5,000 cash deposit that is refundable upon the successful completion of hauling and cleanup activities. The total amount of security being requested will cover both repair and cleanup of any spillage.

Conditions for this hauling process are as follows:

1. Provide equipment in the form of a Front End Loader or two (2) skid steer loaders including operator, trailer and tow vehicle, street sweeper and dump truck to respond within 30-minutes of any reported spill along the haul route.
2. Distribute the haul route and hours of operations to all haul truck operators prior to the hauling operations.
3. Provide "Slow Trucks" signs at designated locations as approved by the City Engineer.
4. Provide a flagman to aid with traffic control at the entrance to the project site.
5. Provide dust control measures including water trucks at the receiving locations.
6. Provide documentation that the trucks being used have passed CHP and/or DMV inspections within the past 12-months.
7. Violations of any of these conditions will result in the stoppage of work until such time that a Safety and Compliance meeting can be held with the Inspector and City Engineer.

### **Fiscal Impact**

Riverside Construction Company, Inc., contractor, pursuant to the plans and specifications, will be responsible for any damage occurring to City Streets, and will place security with the City to guarantee such.

### **Exhibits**

- A – Haul Route Vicinity Map
- B – Haul Route Questionnaire