

R&R Roofing & Waterproofing, Inc.
951-245-0200
17995 Collier Ave
Lake Elsinore CA 92530



City of Lake Elsinore
Daniel Saavedra
Lake Elsinore CA

Estimate # 0000779
Estimate Date March 22, 2021
Estimate Total (USD) \$125,475.00

Item	Description	Unit Cost	Quantity	Line Total
1	Fire Station 97 Site Address: 41725 Rosetta Canyon Dr. -Pick up and Relay 2 Piece Clay tile -Pulling of all existing roofing tiles and stacking accordingly -Supply and install two layers of ASTM 30lb felt underlayment -Supply and replace any damaged and/or missing flashing metals; roof jacks, valleys, tile pan, bird stop, eve riser, etc. -Refasten and secure all pulled roofing tiles back into place -Supply and replace any damaged roofing tiles throughout the process with similar like tile (exact match cannot be guaranteed, but like tiles will be installed at low visibility area of roof) -Supply and replace any damaged and/or missing ridge nailers -Re-cement all hip, ridge and bullnose corners according to manufacturers specification -Reseal and paint all flashing and vents to match upon completion.	1,195.00	105	125,475.00
Exclusions	Any and all things not listed on the above scope of works. Exclusions included multiple layers of tear off , each additional layer will be added charge. R&R can get exact cost of tear off if allowed to take core samples of Roof systems to check for insulation and layers of Roofing systems. Exclusion also include Metal Coving Cap. Please read each scope of work carefully and R&R will gladly provide pricing for any items City is considering.	0.00	1	0.00
DIR Number	DIR#1000048273 - Pricing Based on Prevailing Wage Rates	0.00	1	0.00

Estimate Total (USD) \$125,475.00

To view your estimate online Go to <https://rrroofing-receivables.freshbooks.com/view/3wAKBVfYHp4rtPYn>